

HARBOR BUILD | PROJECT BETA

Issued for coordinated procurement and field execution

Outline Specifications

01 GENERAL REQUIREMENTS

Project Beta is a synthetic Harbor Build waterfront-adjacent operations pavilion renovation planned for 2026. This specification sets performance expectations, coordination gates, and record requirements; it is not a permit set or site-access instruction.

- Submit product data with manufacturer limitations and compatible substrate conditions.
- Maintain a digital closeout index organized by section, revision date, and responsible trade.
- Coordinate all penetrations against structural and MEP model issue PB-26.07.29-C.

01 33 00 SUBMITTAL CONTROL

Provide complete submittals before procurement release. Each package shall identify related drawing reference, finish sample, installation sequencing, and quality-control hold point.

- Review is for design intent only; contractor retains means and methods responsibility.
- Use no shared Project Alpha budget figures; CO-014 is an Alpha-only contextual reference.

01 45 00 QUALITY MANAGEMENT

Use mockups where indicated, photograph concealed-work inspections, and record deviations with disposition before cover-up.

- Field tolerances shall be measured from established control lines.
- Do not substitute products without written equivalency review.

02 EXISTING CONDITIONS

Verify dimensions, utility isolation assumptions, and moisture conditions before selective work. Document discovered conditions with a dated field observation and proposed resolution.

- Protect retained finishes and segregate demolition waste by material stream.

03 CONCRETE AND MASONRY

Provide repair mortars, slab patching, and edge protection compatible with existing substrates. Establish bond, cure, and moisture acceptance records before coatings.

- No structural capacity change is authorized by this outline.

07 THERMAL AND MOISTURE PROTECTION

Maintain a continuous air, water, and thermal control layer through roof-to-wall and opening transitions. Sequence installation to preserve shingle-lap drainage.

- Test representative transitions before repeating the assembly.

09 FINISHES

Use low-emitting interior finish systems and protect completed areas from follow-on trade damage. Match approved mockup sheen, texture, and edge conditions.

- Provide attic stock only when requested in closeout meeting.

22-26 MEP SYSTEMS

Coordinate service clearances, access panels, controls labeling, and commissioning evidence. Final labels shall align with the issued asset schedule.

- Provide functional testing records and training attendance log.