

Concrete Specification

03 30 00 CAST-IN-PLACE CONCRETE

This section covers non-structural slab infill, equipment housekeeping pads, curb repairs, and localized patching for Project Beta. Verify existing reinforcement and embedded services before any sawcut or breakout.

- Submit mix design, curing plan, patch material data, and proposed joint layout.
- Do not begin placement on standing water, frozen substrate, or unaccepted preparation.

MATERIALS

Use normal-weight concrete with 28-day compressive strength appropriate to the documented repair detail; use shrinkage-compensated patch material only where its manufacturer permits the exposure and depth.

- Provide corrosion-resistant dowels where existing reinforcement is exposed and repair detail calls for tie-in.
- Use curing compound only when compatible with subsequent finish or coating.

EXECUTION

Remove unsound material to a sound, clean, profiled substrate. Pre-wet or prime according to repair product instructions; consolidate placement without segregating aggregate.

- Maintain joint locations clear of drains, door thresholds, and equipment anchor zones.
- Protect fresh work from vibration, early loading, and rapid moisture loss.

QUALITY RECORDS

Record ambient conditions, batch tickets, placement area, finishing start, curing method, and repair acceptance. Photograph reinforcement exposure before repair closure.

- Resolve cracks wider than the project acceptance threshold through written disposition.
- Deliver repair map with final closeout package.