

HARBOR BUILD | PROJECT BETA

Issued for coordinated procurement and field execution

MEP Basis of Design

BASIS AND COORDINATION

Mechanical, electrical, and plumbing scope supports a compact operations pavilion with resilient service access and clear asset identification. This document establishes coordination intent, not utility routing or access details.

- Coordinate all sleeves and openings before concrete or enclosure work.
- Maintain BIM issue PB-26.07.29-C as the coordination reference.

MECHANICAL

Provide zoned ventilation and conditioning suitable for intermittent assembly and back-of-house activity. Locate serviceable components behind labeled access panels with manufacturer clearance.

- Commission sequences including occupied/unoccupied setbacks and failure alarms.
- Provide balancing report and final control point list.

PLUMBING

Provide isolation, accessible cleanouts, and water-conserving fixtures consistent with project program. Verify roof drainage interface with envelope trade before closure.

- Pressure-test piping before concealment and document result by zone.

ELECTRICAL AND CONTROLS

Provide dedicated circuits for equipment shown in coordination schedule, emergency lighting test documentation, and readable panel directory updates.

- Separate power and low-voltage pathways; retain bend radius and service loops.
- Label disconnects, controls, and equipment using final asset names.

COMMISSIONING AND CLOSEOUT

Submit startup sheets, O&M data, training agenda, and deficiencies log. Closeout acceptance requires resolved functional checks or a documented owner-approved exception.

- No Project Alpha change-order amount applies to Project Beta.